

Cost of BID document

Rs. 300/-

Ref. GPR/Civil works/2026/

BID DOCUMENT



**Name Of the Work: Repair work of Boundary wall at Govt. Polytechnic Rohru
Distt. Shimla H.P.**

Estimated cost (in Rs.) : 102640/-

Earnest Money (in Rs.) : 10,000/-

Security Money (in Rs.) : 10,000/-

Date & Time of Submission : 14/07/2026 upto 1:00 P.M.

Date of Opening : 14/07/2026 at 3:00 P.M.


Principal
Govt. Polytechnic Rohru

TERMS AND CONDITIONS :

1. Sealed quotation are hereby invited by the Principal Govt. Polytechnic Rohru Distt. Shimla (H.P) for the " *Repair work of Boundary wall at Govt. Polytechnic Rohru Distt. Shimla H.P.* "
2. No advance payment will be made to the contractor before the completion of the work. The final payment will be made only if the civil works committee is fully satisfied with the quality/condition of the work.
3. Quotation should be placed in a sealed cover, with the name of the work written on the envelope which will be received by the Principal office up to 1:00 P.M. on dated 14/07/2026 and will be opened in his/her office on the same day at 3:00 P.M.
4. No quotation will be entertained after the stipulated date and time.
5. The bidder should be registered with HPPWD/Himuda or any other departments approved by H.P. Govt. (Copy of the same should be attached along with bid document.
6. Quotation should accompany earnest money amounting to *Rs 10,000/- (Rupees Ten thousand only)* in the shape of demand draft/FDR/NSS duly pledged in the favour of Principal Govt. Polytechnic Rohru. The tenders without earnest money shall be rejected straight away.
7. The earnest money deposited of the unsuccessful bidders will be returned with in one week of opening of tender.
- 8 . All taxes are the liability of the contractor and he has to pay the same individually in the respective department.
- 9 The successful bidder on award of contract will have to deposit security money amounting to *Rs. 10,000/- (Rupees ten thousand only)* in the shape of demand draft/FDR/NSS to be pledged in favour of principal Govt. Polytechnic Rohru, which will be returned to the bidder after six months of satisfactory performance of works.
10. The material used in the construction should be of good quality/Standards.
11. The quantities of items may be increased or decreased. The final payment will be made as per actual work done.
12. Special care should be taken to write the rates/amount in figure as well as in words, and the amount in figures only in such a way the interpolation is not possible; the total amount should be written both in figures and the words. In case of figures the word Rs should be written before the figures of rupees.
13. Sales Tax or any other tax on material in respect of this contract shall be payable by the contractor and institute will not entertain any claim whatsoever in the respect.
14. Work should be completed within one month after issuing of work order.
15. The quotation can be rejected by undersigned without assigning any reason.
16. The Principal may appoint a "Nagotiation Committee" if required.

Read and Accepted

Signature Of the Contractor



Principal

Govt. Polytechnic Rohru (H.P.)

SCHEDULE OF QUANTITIES

Name of the work :- Repair work of Boundary wall at Govt. Polytechnic Rohru Distt. Shimla H.P.

S. No.	Particular/Detail of items	Qty	Unit	Rates	
				in Fig.	in Words
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50m and lift upto 1.5m, as directed by Engineer-in-charge: All kinds of soil	2.200	Cum		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 20 mm nominal size)	1.100	Cum		
3	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) upto plinth level with : Cement mortar 1:6 (1 cement : 6 coarse sand)	0.900	Cum		
4	Brickwork with common burnt clay F.P.S. (nonmodular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand)	9.800	Cum		
5	12 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand)	67.100	Sqm		
6	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade: New work (Two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	67.1	Sqm		

Note :- The quantities of items may be increased or decreased. The final payment will be made as per actual work done.

Signature of Contractor


 Principal
 Govt. Polytechnic Rohru